


GROUND FLOOR PLAN (4-bed)
Area = 70.09sq.m.
Total Floor Area = 140.18sq.m.


HOUSE TYPE 'B'




SIDE ELEVATION



FRONT ELEVATION




REAR ELEVATION



SECTION 'A-A'


SPECIFICATION NOTES:
 ALL ROOF TIMBERS TO S. 444:1999 TO BE STRESS GRADED AND MARKED ACCORDINGLY AND SIZED TO S.444:1999 WORK TO FIGURED DIMENSIONS ONLY. DO NOT SCALE PRINT.
 ALL HABITABLE ROOMS TO HAVE WINDO W OPENING SECTION MIN. 850x500mm WITH CILL BETWEEN 800-1100 ABOVE F.F.L. ALL CONSTRUCTION METHODS, MATERIALS, INSTALLATIONS AND SERVICES TO BE IN ACCORDANCE WITH ALL IRISH BUILDING REGS & CODES OF PRACTICE AT THE TIME OF CONSTRUCTION. ALL SUB-CONTRACTORS ARE ULTIMATELY RESPONSIBLE FOR ENSURING COMPLIANCE WITH REGULATIONS WITH THEIR OWN TRADE.
 KNAPP PLASTER FINISH ON SCRATCH & SCUDDCO COATS ON 100mm CONCRETE BLOCK EXTERNAL LEAF WITH 50mm CLEAR CAVITY WITH 60mm XTRATHERM XT/CW PARTIAL FILL INSULATION PROVIDING A MAX. U-VALUE OF 0.27W/m2K. WITH 100mm CONCRETE BLOCK INTERNAL LEAF WITH HARDWALL PLASTER FINISH ON SCRATCH & SCUDDCO COATS.
 SIZE AND DEPTH OF A393 MESH REINFORCED STRIP FOUNDATION SUBJECT TO SITE CONDITIONS & ENGINEERS DETAILS. CONC. TO BE MIN. GRADE 15N WITH MIN. OF 75mm COVER TO REINFORCEMENT. ALL FOUNDATIONS TO TABLE 3.4 OF I.S. 326:1995.
 MIN. 150mm POWER FLOATED CONCRETE FLOOR SLAB TO TABLE 3.4 OF I.S. 1988 OR GRADE 15N. ON MIN. 75mm XTRATHERM XT/UF INSULATION WITH 25mm PERIMETER INSULATION OF 0.25 W/m2K THERMAL CONDUCTIVITY ON MONARLEX R.8/B. 300 RADON BARRIER ON 50mm SAND BLINDING ON MIN. 150mm WELL GRADED BROKEN HARDCORE MAX. SIZE 100mm TO MAXIMUM DEPTH 225mm. ENTIRE AREA OF GROUND UNDER DWELLING TO BE STRIPPED, REMOVE ALL TOPSOIL.
 225x75mm S.C.B. TREATED TIMBER PURLIN SUPPORTED AT EVERY 4TH RAFTER WITH 100x44mm S.C.B. TREATED TIMBER STRUT WITH 100x44mm TREATED TIMBER HANGERS & RUNNERS 150x44mm S.C.B. TREATED TIMBER COLLAR AT EVERY 4TH RAFTER.
 PROVIDE OPEN VERTICAL JOINTS AT 900mm C/C FOR DRAINING THE CAVITY. THE CONCRETE FILL SHALL BE SLOPED TO APPROX. 45° AND TROWELLED SMOOTH. TOP OF WHICH SHOULD BE AT LEAST 150mm BELOW D.P.C. LEVEL.
 SELECTED COLOUR P.V.C. GUTTER ON SELECTED COLOUR P.V.C. FASCIA FIXED TO 19mm W.B.P. PLYWOOD GROUNDS WITH 10mm WIDE CONTINUOUS GUIDEVALE SOFFIT VENTILATOR IN ACCORDANCE WITH B.S. 5250 AND BUILDING REGULATIONS PART F WITH SLOTS DESIGNED TO EXCLUDE LARGE INSECTS.
 GABLE WALLS TO BE SUPPORTED ALONG ROOF SLOPE, GROUND & FIRST FLOOR CEILING LEVEL WITH GALVANISED MILD STEEL STRAPS AT 2M CRS. SECTIONAL SIZE 30x5mm TO SPAN AT LEAST 2 JOISTS/RAFTERS & ANCHORED TO UNCOIT CONCRETE BLOCKS RAFTERS & JOISTS TO BE PACKED & NOGGED OFF WALL.
 100x65mm AND 150x65mm PRESTRESSED, PRE-CAST REINFORCED CONCRETE LINTELS WITH 1000 GAUGE STEPPED D.P.C. WITH 50mm HYTHERM EXPANDED POLYSTYRENE PACKED BETWEEN BOTH LINTELS.
 SELECTED COLOUR ROOF TILE/SLATE ON TREATED S.W. 50x35mm S.C.B. TREATED TIMBER RAFTERS AT 400mm c/c IN ACCORDANCE WITH I.S.444:1998.
 ALL STAIRS & BALUSTRADES TO BE CONSTRUCTED IN ACCORDANCE WITH CURRENT BUILDING REGS. T.G.D. K.
 100x75mm TREATED S.W. WALLPLATE SECURED TO INTERNAL LEAF WITH GALVANISED STEEL STRIPS AT 2M CRS. OF MIN. CROSS SECTION 30x5mm CARRIED DOWN MIN. 2 FULL COURSES. WHERE WALL PLATES ARE BUTT JOINTED STRIPS TO BE PROVIDED AT MAX. 400mm EITHER SIDE OF JOINT.
 STAINLESS STEEL TWIST TYPE WALL TIES TO IS EN 845-1:2003 @ 450mm c/c VERTICALLY & 750mm c/c HORIZONTALLY & AT EVERY COURSE AROUND WINDOW AND DOOR OPES.
 200mm MINERAL WOOL INSULATION PACKED BETWEEN ENTIRE AREA OF CEILING JOISTS WITH 50mm XTRATHERM XT/PR BOARD RIGID INSULATION FIXED TO UNDERSIDE OF JOISTS, PROVIDING 0.16W/m2K. THERMAL CONDUCTIVITY WITH 12.7mm FOILBACKED PLASTERBOARD WITH HARDWALL PLASTER FINISH.
 (0.20W/m2K U-VALUE REQUIRED IF INSULATION IS IN SLOPE OF ROOF) INSULATION USED THROUGHOUT THE DWELLING/BUILDING MUST COMPLY WITH THE NEW BUILDING REGS. (T.G.D. - DWELLINGS - Building Regs. 2002)
 FIRST FLOOR CONSTRUCTION TO CONSIST OF:
 150x22mm S.W. T&G FLOOR BOARDS ON 225x44mm S.W. S.C.B. FLOOR JOISTS AT 400mm CRS. WITH SOLID BRIDGING AT 1350mm CRS. WITH 12.5mm PLASTER SLAB & HARDWALL PLASTER FINISH. ALLOW 18mm W.B.P. PLYWOOD FLOOR TO BATHROOM TO ALLOW FOR A NON-SLIP FLOOR TILE FINISH.
 STUD PARTITIONS TO CONSIST OF:
 S.W. STUDS AT 400mm CRS. WITH 2 NO. ROWS OF NOGGINGS 75x35mm STUDS TO HIGH LOAD-BEARING WALLS, 100x44mm STUDS TO LOAD-BEARING WALLS WITH DOUBLE HEADER AND SOLE PLATES. MAX. MOISTURE CONTENT OF 22% FINISHED WITH 3mm GYPSUM HARDWALL PLASTER FINISH ON 9.5mm PLASTER SLAB TO BOTH SIDES.
 DOOR HANDLES SHOULD BE LOCATED AT A HEIGHT OF 900-1200mm ABOVE INTERNAL FLOOR LEVEL. ELECTRIC LIGHT SWITCHES SHOULD BE LOCATED AT A SIMILAR HEIGHT. (T.G.D. M Building Regs 2000)
 DOORS TO HABITABLE ROOMS TO HAVE CLEAR OPENING WIDTHS OF:
 a) 750mm if corridor is 1200mm wide.
 b) 775mm if corridor is 1050mm
 c) 800mm if corridor is 900mm
 (T.G.D. M Building Regs 2000)
 INSTALL 225mmØ SPIGGOT AND SOCKET FLUE LINER WITH SOCKET FACING UPWARDS. PACK FLUE LINERS AS EACH LINER IS BUILT IN WITH 1/12 CEMENT LIME AND SAND MIX. MIX TO BE WETTED WITH WATER. FLUE LINER TO BE KEPT A MIN. OF 50mm FROM SURROUNDING BLOCKWORK. INSTALL PRE-CAST CONC. CAPPING, WEATHERED ON TOP AND TREATED UNDERNEATH. FORM 50mm CHASE IN CHIMNEY STACK. NOT LESS THAN 150mm ABOVE ROOF. FINISH & RETURN CODE 5 LEAD FLASHING INTO SAME. WEDGE WITH LEAD WEDGES SEAL WITH COLOURLESS MASTIC. FORM BELL CAST OVER USING EXPANDED METAL BEAD.
 150 POWER FLOATED CONCRETE FLOOR SLAB ON 100mm HYTHERM EPS UNDER FLOOR INSULATION WITH 25mm PERIMETER UPGRADE ON EXISTING SCUDDCO COATS. FULLY COMPACTED HARDCORE MIN. 225mm THICK IN ACCORDANCE WITH BUILDING REGS. PART L 2002. PROVIDING U-VALUE OF 0.25W/m2K IN FLOOR.
 2 NO. PRE-CAST CONCRETE LINTELS TO S.E. DESIGN, 150x75mm LINTEL TO INT. LEAF WITH 1 NO. 100x75 LINTEL TO EXTERNAL LEAF. INSULATION PACKED INTO CAVITY TO PREVENT COLD BRIDGING.
 300 TWIN LEAF CAVITY CONSTRUCTION OF 100mm CONC. BLOCK INT. LEAF WITH 100mm CONC. BLK. EXT. LEAF WITH 1:1.5 MIX MORTAR WITH 50mm XTRATHERM XT/CW PARTIAL FILL INSULATION WITH 35mm CLEAR CAVITY.
 SELECTED COLOUR P.V.C. DOUBLE GLAZED WINDOWS TO MANUFACTURERS DETAIL WITH U-VALUE OF MIN. 2.2W/m2K IN ACCORDANCE WITH BUILDING REGS. PART L 2002.
 SELECTED COLOUR P.V.C. GUTTER WITH SELECTED COLOUR MATCHING RAINWATER GOODS.
 SELECTED KNAPP PLASTER TO REAR ELEVATION WITH SELECTED BRICK FORMING SOLDIER COURSE OVER WINDOWS.
 200mm MINERAL WOOL INSULATION PACKED BETWEEN JOISTS WITH 50mm XTRATHERM XT/PR BOARD WITH 12.5mm PLASTERBOARD & SKIM.
 SELECTED BLUE/BLACK ROOF TILE OR SLATE ON 50x35mm TREATED S.W. TILING BATTENS ON SARKING FELT TYPE '1P' TO MAIN ROOF WITH TYPE 'SU' AT EAVES. ON 110x25mm TREATED TIMBER RAFTERS AT 400mm C/C IN ACCORDANCE WITH I.S.444.
 SELECTED COLOUR P.V.C. GUTTER ON SELECTED COLOUR P.V.C. FASCIA FIXED TO 19mm W.B.P. PLYWOOD GROUNDS WITH 10mm WIDE CONTINUOUS GUIDEVALE SOFFIT VENTILATOR IN ACCORDANCE WITH B.S. 5250 & BUILDING REGS PART F.
 SELECTED COLOUR P.V.C. DOUBLE GLAZED SLIDING DOUBLE PATIO DOORS WITH U-VALUE OF MIN. 2.2W/m2K IN ACCORDANCE WITH BUILDING REGS. PART L 2002.
 EXTRACT PIPE FROM RADON SUMP. TERMINATES OUTSIDE DWELLING IS CAPPED & MARKED TO IDENTIFY ITSELF.
 100mm Ø EXTRACT PIPE FROM RADON SUMP.
 900x300 1:2.4 MIX CONCRETE STRIP FOUNDATION INCORP A252 MESH REINFORCEMENT 40mm FROM END OF FOUNDATION.
 9.325M OVERALL WIDTH




FIRST FLOOR PLAN



FRONT ELEVATION



REAR ELEVATION



SECTION 'A-A'

APPROACH - T.G.D.M
 MINIMUM CLEAR OPENING OF 800mm TO EXTERNAL ACCESS DOOR. 750mm CLEAR OPE. TO ALL INTERNAL DOORS. AN UN-OBSTRUCTED SPACE OF 300mm ON LEADING SIDE OF DOOR. ALL ABOVE IN ACCORDANCE WITH BUILDING REGS. 2000-PART M.
 MIN. 900mm WIDE LEVEL OR RAMPED APPROACH TO MAIN ENTRANCE SUITABLE FOR WHEELCHAIR ACCESS.
 EITHER A GENTLY SLOPING RAMP / LEVEL ACCESS MUST BE PROVIDED TO THE MAIN ENTRANCE OF all other entrances where this is practicable) OF THE DWELLING. THERE SHOULD BE A CLEAR AREA OF 1200x1200mm SQ. IN FRONT OF THIS ENTRANCE. THE MAX. THRESHOLD MUST NOT EXCEED 15mm (TGD M Building Regs 2000)
VENTILATION - T.G.D.F
 ALL BELOW IN ACCORDANCE WITH TGD F BUILDING REGS 2002.
 ALL HABITABLE ROOMS REQUIRE A VENTILATION OPENING (STANDARD 225x225 WALL VENT) HAVING MIN TOTAL AREA 4500 SQ MM WITH RAPID VENTILATION (WINDOW OPE) OF MIN. 5% FLOOR AREA OF ROOM. KITCHENS & UTILITY ROOMS REQUIRE A VENTILATION OPE (STANDARD 225x225 WALL VENT) HAVING MIN TOTAL AREA 6500 SQ MM WITH RAPID VENTILATION (WINDOW OPE) OF MIN. 5% FLOOR AREA OF ROOM. IN ADDITION TO MECHANICAL VENTILATION TO EXTRACT MIN 60 LITRES PER SEC. (OR 30 LITRES PER SEC IF VENT EXTRACT IS INCORPORATED IN A COOKER HOOD)
 ALL BATHROOMS (WITH OR WITHOUT WC'S) REQUIRE RAPID VENTILATION (WINDOW OPE) MIN 5% OF FLOOR AREA OF ROOM WITH A MECHANICAL EXTRACT VENT TO EXTRACT MIN 15 LITRES PER SEC.
 WALL VENTS TO CONSIST OF:
 225x225mm GALVANISED LOUVRE EXTERNALLY WITH 225x225mm P.V.C. HIT AND MISS VENT INTERNALLY WITH 150mm U.V.C. PIPE CARRIED ACROSS CAVITY WALL AND A MIN. OF 17mm ABOVE FINISHED FLOOR LEVEL.
 PROVIDE 25mm WIDE CONTINUOUS GUIDEVALE SOFFIT VENT AT EAVES IN ACCORDANCE WITH B.S. 5250 AND BUILDING REGULATIONS PART F.
 PROVIDE VENTILATION AT THE RIDGE AT LEAST EQUAL TO CONTINUOUS VENTILATION RUNNING THE LENGTH OF THE RIDGE & 5mm WIDE
RADON - T.G.D.C 2004
 AS A REQUIREMENT OF TGD C. EACH NEW DWELLING / EXTENSION MUST AS A MINIMUM PROVIDE A RADON SUMP BOX WHICH IS PIPED TO A POINT OUTSIDE OF THE HOUSE FOOTPRINT. ONE SUMP BOX PER MAX. 250 SQ M. ALL SUMP BOXES TO BE CENTRALLY NO MORE THAN 15M FROM ANY OUTSIDE WALL. IN ALL OTHER CASES 2 SUMP BOXES TO BE PROVIDED. IN CERTAIN AREAS A RADON BARRIER TO BE USED. IT IS ADVISED THAT A BUILDER INSTALL A RADON BARRIER. ONE INSTALLED CORRECTLY, IT IS NOT NECESSARY TO INSTALL A D.P.M. ALL PIPEWORK COMING FROM SUMP TO HAVE SEALED JOINTS & BE SEALED THROUGH THE CAVITY. IT MAY BE NECESSARY TO PROVIDE FREE AIRWAYS TO THE RISING WALLS.
 ALL RADON BARRIER JOINTS & SERVICES MUST BE FULLY SEALED. JOINTS SHOULD BE FORMED USING TWO STRIPS OF MONARBOARD SEAL AROUND SERVICE PIPES AND CABLE PENETRATIONS USING A MONARLEX TOP HAT SECTION.
 IN HIGH RADON AREAS, I.E. AREAS WITH MORE THAN 10% OF THE HOUSES HAVING A RADON LEVEL EXCEEDING THE NATIONAL REFERENCE LEVEL OF 200Bq/cubic m. A SEALED RADON MEMBRANE WITH MEANS OF EXTRACTING RADON, I.E. A SUMP/SUMPS SHALL BE PROVIDED, & WILL BE ACTIVATED BY A FAN. ALL IN ACCORDANCE WITH T.G.D.C. OF CURRENT BUILDING REGS.
PART 'L' BUILDING REGS 2002
 TOTAL AREA OF ALL OPES-DOORS/WINDOWS NOT TO EXCEED 25% OF TOTAL FLOOR AREA TO COMPLY WITH PART 'L' OF BUILDING REGS.
FIRE SAFETY - T.G.D.B 2006
 WINDOWN ESCAPE
 ALL HABITABLE ROOMS TO HAVE CLEAR WINDOW OPENING AREA MIN. 0.33m2 WITH MIN. WIDTH & HEIGHT OF 450mm. BOTTOM OF OPENING SHOULD BE NO MORE THAN 800-1100 ABOVE F.F.L.
 WHERE CILL LEVELS ARE LESS THAN 800mm ABOVE INTERNAL FLOOR LEVEL, GUARDING/GLAZING MUST BE PROVIDED IF GUARDING CONTAINS GLAZING IT SHOULD BE IN ACCORDANCE WITH REQUIREMENTS OF BS 6262:4. (TGD K Sect 2.2, Building Regs 1997)
 GLAZING AT CRITICAL LOCATIONS TO BE TOUGHENED AND IN ACCORDANCE WITH THE REQUIREMENTS OF BS 6262 Pt.4. (TGD K Sect 2.2 Building Regs 1997)
 IN THE CASE OF A DORMER WINDOW, THE DISTANCE FROM THE EAVES TO THE BOTTOM OF THE OPENING SECTION OF WINDOW, MEASURED ALONG THE SLOPE OF THE ROOF, SHOULD NOT EXCEED 1.7M
 AN LD1 OR LD2 TYPE FIRE DETECTION & ALARM POWERED INTERCONNECTED SYSTEM SHOULD BE PROVIDED & INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF BS 5839 Pt.6 2004 (TGD B 2006)
 PARTY WALLS SHALL RUN VERTICALLY THE FULL HEIGHT OF THE DWELLING, TO THE UNDERSIDE OF THE ROOF, WITH ROOF BEDDED IN NON-COMBUSTIBLE FIRE STOPPING MATERIAL ON TOP OF WALL.

Total Floor Area = 140.18sq.m.

WILLIAM HOGAN & Associates Architects
 St. Catherine's Hall, Catherine St., Waterford.
 Tel: 051- 853633/841242 Fax: 051- 841242. Mobile: 087- 2227652.
 Email: billwhog@eircom.net , raywhog@eircom.net , grainnewhog@eircom.net

JOB: Proposed Housing dev. at Abbeyside, Dungarvan
 TITLE: House Type B- 4-BED
 SCALE: 1:100 DWG. NO.: 1747-06 R04
 DATE: Dec. 2007

HOUSE TYPE B- 4-BED on SITES 138-141